405 Improvement work will result in closure of freeway in late night early morning hours starting Saturday Aug. 29

OCTA Crews will install pre-cast concrete girders for the Fairview Bridge over I-405, requiring full closures of 405 Freeway during early morning hours starting Saturday Aug. 29.

The girders are the main horizontal support beams, known as the superstructure, for the new bridge. They are installed across the bridge’s substructure, the abutments and center columns. Pre-cast girders are used instead of installing falsework and pouring the superstructure in place.

This work will require northbound (NB) and southbound (SB) full freeway, lane and ramp closures, as well as the closure of Fairview between McCormack Lane and South Coast Drive. Residential access will be maintained.

Click the links below for map detours.

Local detours.

Freeway detours.

Click to see closures and detours on the interactive map

Closures are set for:

Night One
As early as 11 p.m. Saturday, Aug. 29, to 9 a.m. Sunday, Aug. 30
Night Two

As early as 10 p.m. Monday, Aug. 31, to 5:30 a.m. Tuesday, Sept. 1

Night Three

As early as 10 p.m. Tuesday, Sept. 1, to 5:30 a.m. Wednesday, Sept. 2*

Additional Nights: 11 p.m. to 5 a.m. for several weeknights.

*SB I-405 will be closed, and access to NB I-405 will be maintained.

Some activity also may occur during the day.