Asphalt and concrete work completed on Adams Ave.

The Public Services Department recently completed a two-inch grind of the roadway pavement on Adams Avenue from Fairview Road to Peterson Place and overlaid a new rubberized asphalt pavement.

Grinding and the construction of 3,400 tons of asphalt rubberized hot mix to create a new two-inch surface layer was completed late April.

Work was coordinated with the Orange Coast College Programs, Swap Meet, local temporary Fire Station, adjacent residents' and businesses. Prior to this work, CJ Concrete Construction was contracted to remove and replace damaged curbs, gutters, sidewalks, and wheelchair ramps along this segment of Adams Ave.

Final construction activities including utility adjustments, lane and traffic legend striping, and traffic loop detectors were completed last week.